

## Attachment 4 - Quote - Boden Building(2)



### QUOTE

Wakatipu Anglican Parish

**Date** 9 Jan 2023  
**Expiry** 27 Nov 2022  
**Quote Number** QU-0056  
**Reference** St Paul's Arrowtown  
**GST Number** 98-209-336

Boden Building Ltd  
56 Norfolk Street  
Arrowtown 9302  
Attn: Bod

#### St Paul's Arrowtown

Description	Quantity	Unit Price	Amount NZD
Boden Building to strip Church roof and apply roofing underlay and reinstate existing iron, using new fasteners and hidden modern flashings under originals	210.00	85.00	17,850.00
QT Roof for all modern flashings, fasteners and underlay	1.00	2,400.00	2,400.00
True Colours to wash and prep Church roof and paint in matching colour	1.00	10,952.70	10,952.70
Fallproof scaffold to provide all platforms and edge protection for above mentioned works	1.00	7,206.65	7,206.65
For the following NORTH refers to the Berkshire St elevation. Boden Building to cut away and replace all rotten timber to north elevation, including all boards which abut the porch apron flashing.	1.00	1,660.00	1,660.00
To restore and patch 2 number porch doors including fascia	1.00	1,700.00	1,700.00
To restore north east internal corner, porch to main body and to apply 2 rainwater diverters to apron flashings	1.00	1,220.00	1,220.00
All timberwork to East elevation ready for painting including 4 number replacement window sills and 2 base weatherboards	1.00	3,527.50	3,527.50
South trimming and patching various boards to apron flashings and installing 2 rainwater diverters to apron flashings	1.00	850.00	850.00
West elevation all timber work including 4 number replacement sills and baseboards	1.00	3,527.50	3,527.50
Bell tower strengthen and reflash and re rope in water tight manner	1.00	965.00	965.00

Description	Quantity	Unit Price	Amount NZD
P'n'G for all the above, including rubbish disposal, tooling, PPE, SSSP, back office work, insurance and underground storm water inspection	1.00	6,500.00	6,500.00
True Colours to paint all timberwork on church from spouting down to ground level in existing colour scheme	1.00	27,005.45	27,005.45
Upgrade 2 number downpipes to main roof of church only	1.00	1,850.00	1,850.00
Contingency	1.00	8,000.00	8,000.00
		Subtotal	95,214.80
		TOTAL GST 15%	14,282.24
		<b>TOTAL NZD</b>	<b>109,497.04</b>